

TEST REPORT



Power Testing & Technology Institute

R414-0725**Test Report**

| | |
|-----------------------|---|
| APPARATUS | <u>VCS (Vacuum Contactor Switch)</u> |
| TYPE | VC-6G-44EE |
| RATINGS | 3 Poles, 50/60 Hz, 7.2 kV, 400 A, 4 kA |
| STANDARD | IEC 62271-106(2011) |
| PERFORMED TEST | Verification of coordination with SCPDs |
| REQUEST DATE | April 14, 2014 |
| DATE OF TESTS | February 07, 2014 |
| CLIENT | LSIS Co., Ltd. |
| MANUFACTURER | LSIS Co., Ltd. |

Test result

The tests have been carried out in accordance with the instructions of the applicant.

The test results are presented in the record of tests with the performance of the apparatus tested and the observations made during the tests. The oscillograms are attached hereto.

The test results apply only to the specific samples tested.

This document shall not be reproduced except in full, without a written approval of PT&T.

Number of pages : total(18), cover(1), records(11), Oscillogram(6)



LSIS Co.,Ltd

Prepared **Huh, Dae-Haing** Test Engineer

Approved **Park, Ji-Hoon** Technical Manager

Date of issue **April 24, 2014**

**LSIS Co.,Ltd. Power Testing & Technology Institute**

95, Baekbong-ro, Heungdeok-gu, Cheongju-si, Chungcheongbuk-do, Korea, 361-720
Tel: +82-(0)43-261-6587, Fax: +82-(0)43-261-6628, E-mail: bksung @lsis.biz

Client

Bae Sang Kyu

Address

LSIS Co., Ltd.

95, Baekbong-ro, Heungdeok-gu, Cheongju-si,
Chungcheongbuk-do, Korea, 361-720**Witnessed by**

Bae Sang Kyu

Address

LSIS Co., Ltd.

95, Baekbong-ro, Heungdeok-gu, Cheongju-si,
Chungcheongbuk-do, Korea, 361-720**Contents**

| | |
|--------------------------|----------|
| Apparatus designation | Page 3 |
| Table of performed tests | Page 4 |
| Test results | Page 5~7 |
| Test circuit condition | Page 8 |
| Test circuit diagram | Page 9 |
| Photographs | 3 sheets |
| Circuit drawing | - |
| Oscillograms | 6 sheets |

The measurement uncertainty of the test results in this document is maximum 5 % for voltage, current and time. Which is estimated at the level of twice the standard deviation (corresponding to a confidence level of 95 % for the coverage factor of 1.96 in the case of normal distribution).

Apparatus designation by the client

| | |
|--------------|------------------|
| Apparatus | Vacuum Contactor |
| Manufacturer | LSIS Co., Ltd. |
| Type | VC-6G-44EE |

Rating

| | |
|--------------------------------------|------------|
| Number of poles | 3 |
| Rated frequency | 50/60 Hz |
| Rated voltage | 7.2 kV |
| Rated normal current | 400 A |
| Power frequency withstand voltage | 20 kV |
| Lightning impulse withstand voltage | 60 kV |
| Rated short-circuit making current | 10.4 kAp |
| Rated short-circuit breaking current | 4 kA |
| Rated short-time withstand current | 6.3 kA |
| Rated duration of short-circuit | 1 s |
| Rated opening time | ≤ 40 ms |
| Rated closing time | ≤ 100 ms |
| Closing devices | 110 V d.c. |
| Opening devices | 110 V d.c. |
| Motor | 110 V d.c. |




Table of performed tests

| Test item | Test result | Date | Page |
|--|-------------|------------|------|
| 1. No load operation checks | - | - | 5 |
| 2. Verification of coordination with SCPDs | - | - | - |
| 2.1 Rated short circuit breaking current | Passed | 2014.02.07 | 6 |
| 2.1 Rated short circuit making current | Passed | 2014.02.07 | 7 |
| Under blank | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| Test results | | | |
| <ul style="list-style-type: none"> - No visible damage was observed. - After the test, the test object was operated correctly. | | | |

1. No load operation checks

| Test condition | Osc. no. | Operating sequence | Control voltage (V d.c) | | Closing time ms | Opening time ms |
|---|--|--------------------|-------------------------|--------|-------------------------|----------------------|
| | | | C V | O V | | |
| After verification of coordination with SCPDs | 1410 0780 | CO | 93.5 | 93.5 | 118.7 120.3 119.8 | 28.0 27.7 28.5 |
| | 1410 0781 | CO | 110 | 110 | 100.2 101.8 101.3 | 25.3 25.0 25.7 |
| Condition during and after the test | - The test object was operated normally. | | | | | |



2. Verification of coordination with SCPDs

2.1 Test duty A - 100 % break tests

| Test condition | | | | | |
|-------------------|---|---|--------------------------------|------------------------------|--|
| Standards | | IEC 62271-106:2011 | | | |
| Operation duty | | O x 1 | | | |
| Circuit condition | Test circuit | GMD3S | | | |
| | Frequency | 60 Hz ^{+10 %} | | | |
| | Applied voltage | - | | | |
| | Recovery voltage | 7.2 kV ^{±5 %} , Duration ≥ 0.3 s | | | |
| | Breaking current | 40 kA ^{+5 %} | | | |
| | Making current | 104 kA ^{+5 %} | | | |
| Power factor | | Average ≤ 0.15 | | | |
| Operating voltage | Closing coil | 85 % of the rated voltage | | | |
| | Opening coil | 85 % of the rated voltage | | | |
| TRV | Classification | Peak value (u _c) | Time to peak (t ₃) | Delay time (t _d) | Rate of rise (u _o /t ₃) |
| | Standards | 12.4 kV | 104 μs | - | 0.119 kV/ μs |
| | Measured value (30% calibration) (Osc. No 14100760) | 4.2 kV | 61.3 μs | - | 0.228 kV/ μs |

| Results | | | | | | | | | | | |
|----------------------------------|----------------|--|----------------------------|----------------------|----------------------|--------------------------|--------------|-----------------|-----------------------|------------------------|-----------------|
| Condition before the test | | New specimen | | | | | | | | | |
| Osc. No. | Interval | Applied voltage (Phase to earth) kV | Cut off current peak kA | Recovery voltage | | | Making angle | Close time s | Fuse break time ms | Total break time ms | Result |
| | Operation duty | | | Phase to earth kV | Phase to phase kV | TRV u _c kV | | | | | |
| 1410 0760 | - | - | (12.38) | - | - | - | - | - | - | - | 30% Calibration |
| | | - | (12.43) | - | - | - | - | - | - | - | |
| | | - | (12.14) | - | - | - | - | - | - | - | |
| 1410 0769 | O | - | 33.8 | 4.2 | 7.3 | - | - | - | 8.0 | - | Passed |
| | | - | -51.7 | 3.5 | 6.1 | - | - | - | 5.4 | - | |
| | | - | 30.5 | 5.2 | 9.0 | - | - | - | 8.2 | - | |
| Condition during and after tests | | <ul style="list-style-type: none"> - No visible damages were observed. - Note. () means rms value of short-circuit current. | | | | | | | | | |

2.2 Test duty B - 100 % make tests


| Test condition | | | | | |
|-------------------|---|--|--------------------------------|------------------------------|--|
| Standards | | IEC 62271-106:2011 | | | |
| Operation duty | | C x 1 | | | |
| Circuit condition | Test circuit | GMD3S | | | |
| | Frequency | 60 Hz ^{±10%} | | | |
| | Applied voltage | 7.2 kV ^{+10%} | | | |
| | Recovery voltage | 7.2 kV ^{±5%} , Duration ≥ 0.3 s | | | |
| | Breaking current | 40 kA ^{+5%} | | | |
| | Making current | 104 kA ^{+5%} | | | |
| | Power factor | Average ≤ 0.15 | | | |
| Operating voltage | Closing coil | 85 % of the rated voltage | | | |
| | Opening coil | 85 % of the rated voltage | | | |
| TRV | Classification | Peak value (u _c) | Time to peak (t ₃) | Delay time (t _d) | Rate of rise (u _c /t ₃) |
| | Standards | 12.4 kV | 104 μs | - | 0.119 kV/ μs |
| | Measured value (30% calibration) (Osc. No 14100760) | 4.2 kV | 61.3 μs | - | 0.228 kV/ μs |

| Results | | | | | | | | | | | |
|----------------------------------|----------------------------|---|----------------------------|----------------------|----------------------|--------------------------|--------------|-----------------|-----------------------|------------------------|-----------------|
| Condition before the test | | After test duty A – 100% break tests | | | | | | | | | |
| Osc. No. | Interval Operation duty | Applied voltage (Phase to earth) kV | Cut off current peak kA | Recovery voltage | | | Making angle | Close time s | Fuse break time ms | Total break time ms | Result |
| | | | | Phase to earth kV | Phase to phase kV | TRV u _c kV | | | | | |
| 1410 0760 | - | - | (12.38) | - | - | - | - | - | - | - | 30% Calibration |
| | | - | (12.43) | - | - | - | - | - | - | | |
| | | - | (12.14) | - | - | - | - | - | - | | |
| 1410 0776 | C | 4.3 | - | - | 10.4 | - | - | - | - | - | Passed |
| | | 4.4 | -45.8 | 4.5 | | - | - | | 4.7 | | |
| | | 4.4 | 45.6 | -4.7 | | - | - | | 4.7 | | |
| Condition during and after tests | | <ul style="list-style-type: none"> - No visible damages were observed. - The fuse of phase (R) did not melt. - Note. () means rms value of short-circuit current. - Power frequency recovery voltage was not maintained for 0.3s due to equipment problems | | | | | | | | | |


■ Test circuit condition

| | | | | | | |
|-------------------------|--|-------|--|--|--|--|
| Test Items | Coordination with SCPD tests | | | | | |
| Test circuit | GMD3S | | | | | |
| Number of phases | 3 | | | | | |
| Frequency (Hz) | 60 | | | | | |
| Generator connections | Y | | | | | |
| Generator neutral | Not earthed | | | | | |
| Transformer connections | Δ/Δ | | | | | |
| Transformer ratio (kV) | 18/8.6 | | | | | |
| Transformer neutral | Not earthed | | | | | |
| Short-circuit point | Earthed | | | | | |
| Load neutral point | - | | | | | |
| Supply circuit | Impedance (Ω) | 2.110 | | | | |
| | Power factor | <0.15 | | | | |
| TRV Control elements | Resistance R1 (Ω) | - | | | | |
| | Capacitance C1 (μF) | 0.99 | | | | |
| Load circuit | Resistance R _L (Ω) | - | | | | |
| | Reactance L _L (mH) | - | | | | |
| | Capacitance C _L (μF) | - | | | | |


■ Test circuit diagram GMD3S



■ Verification of coordination with SCPDs




<Before test>




<Before test duty A - 100 % breaking tests>

■ Verification of coordination with SCPDs




<Before test duty B - 100 % making tests>

DTCT




<After test duty A - 100 % breaking tests>



■ Verification of coordination with SCPDs





<After test duty B - 100 % making tests>













Date : 2014-02-07 4:50:42 오후
 Rec. No. : 14100776







충북 청주시 흥덕구 백봉로 95(송정동) (우 361-720)
 Baekbong-ro 95, Heungdeok, Cheong Ju, 361-720, Korea
 Tel. +82-(0)43-261-6587 Fax. +82-(0)43-261-6628 E-mail. IPT@ptt.com

PT&T는 KOLAS 국제공인시험기관으로서 시험을 다음과 같이 4가지로 구분하고 이에 대한 성적서를 발행합니다.

- | | |
|------|---|
| 개발시험 | 규정된 절차에 따라 명확히 검정된 피시험품에 대해 국가규격, 국제규격등에 정해진 개발시험 요건에 따라 제조자가 부여한 모든 정격특성 및 정격성능에 대한 시험 |
| 성능시험 | 개발시험 항목중 일부의 정격특성 및 정격성능에 대해 개발시험 절차 및 요건에 따른 시험 |
| 항목시험 | 개발시험절차와 공인규격 또는 기술기준에 따라 시험했으나, 시험항목이 충족되지 않는 경우 |
| 참고시험 | 시험 의뢰자의 요구조건에 따른 시험 |

PT&T, is a KOLAS-accredited testing and calibration laboratory, and issues test reports in four types as followings.

- | | |
|--------------------------------|--|
| TYPE TEST REPORT | is issued to prove and to verify that a duly and clearly identified equipment is satisfactory to the type test requirements of a recognized standard with respect to all the rated characteristics and performance |
| PERFORMANCE TEST REPORT | is issued to prove and to verify only a part of the rated characteristics and performance is satisfactory to all the requirements and procedures as of type test |
| TEST REPORT – I | is issued for the tests followed type test procedure and in accordance with a recognized standard but incomplete to form type test or performance test |
| TEST REPORT – II | is issued for the tests carried out in accordance with the instructions of the client |